



(Previously Known as Mother Dairy, Gandhinagar)

### **Request for Quotation (RFQ)**

AFD: PUR: HSG: Mezzanine.

31 May, 2025

To,

Dear Sir,

Sub: **Request for Quotation (RFQ)** for “Mezzanine structure for roll room” as mentioned in annexure.

We invite your most competitive offer for Mezzanine structure for roll room as per detailed specifications. Your offer should be based on following considerations.

1. The offer should submit on portal:-AmulFed Dairy (Previously known as Mother Dairy-A Unit Of GCMF Ltd) Plot No-35, Nr. Indira Bridge, Ahmedabad - Gandhinagar Highway. Village Bhat, Dist - Gandhinagar. Pin - 382 424.

2. Due Date: **Technical due June 07, 2025 before 16:00 hours.**

**Commercial due June 09, 2025 before 17:00 hours.**

3. The offer should be submitted in portal only. First of all, register your firm on shared link.
4. Offer received after due date for whatsoever reason may be rejected.
5. Offer should valid for acceptance for 90 days from date for submission of offer.
6. The price should be quoted with all details.
7. **Specify your tax condition.** Non indication of above levies will mean that prices are inclusive of all taxes and above levies.
8. Realistic and earliest completion period should be indicated in offer.
9. It will not be binding on us to accept the lowest offer.
10. Right to accept/reject any/all offers without assigning reason is reserved by us.
11. Offers which are incomplete or not meeting the conditions are liable for rejection.
12. Payment terms after successful trial run @ plant within 30 days. If the payment term is document through bank, all banking charges shall be borne by the suppliers.
13. **Please find below link to register your firm on Purchase Portal. Without completing registration process on portal can't submit offer.**

**First of all, register your firm on shared link so can send inquiry through portal only.**



(Previously Known as Mother Dairy, Gandhinagar)

Interested bidders have to register your firm in our Purchase portal.

Website for our portal is as >>>: <http://afdpurchase.amul.in/>

Click Below links for Guidelines :

1. [Guide for VRF - MANUFACTURERS](#)

14. **Eligibility criteria: Must have executed similar type of order in last 5 year. Share credentials of the same. If required we ask for Performance Bank Guarantee.**
15. **Once registration process completes, we invite vendor to submit offer. Vendors need to submit technical first only after technical clearance you will be able to submit commercial figures.**

We are an ISO 9001: 2015, ISO 14001:2015, ISO 22000:2018, ISO 50001:2018 and ISO 45001:2018 company; we follow sustainable eco-friendly processes in our organization and expect the same to be followed at your end. We emphasis on energy efficient system and utilization of renewable energy systems in eco-friendly and sustainable way.

Note: If required please visit premises with prior confirmation before quote. Please arrange visit between 2:00 P.M. to 5:00 P.M. in working day.

: We may go for reverse auction/negotiation. If required we may ask for PBG.

Mail id as mentioned below.

Shri Hardik Gajjar : [hardik.gajjar@amul.coop](mailto:hardik.gajjar@amul.coop)

Shri Bhargav Kanabar : [bhargav.kanabar@amul.coop](mailto:bhargav.kanabar@amul.coop)

Shri Chandrakant Trivedi : [chandrakant.trivedi@amul.coop](mailto:chandrakant.trivedi@amul.coop)

Yours Faithfully,

For AmulFed Dairy,

Purchase Depart.

# AmulFed Dairy

A UNIT OF GUJARAT CO-OPERATIVE MILK MARKETING FEDERATION LIMITED

(Previously Known as Mother Dairy, Gandhinagar)

Sr.NO.	TECHNICAL SPECIFICATIONS	VENDOR COMPLIANCE
<u>1</u>	<p><b>Description of Work :</b> Design, Fabrication, Sly, Installation of <u>Mezzanine flooring system and Storage at Roll Room at AmulFed dairy as per the load details &amp; Dimension given below: -</u></p> <p><b>Quantity Required: 1 Lot</b></p>	
<u>2</u>	<p><b>Note:</b> <u>Before quoting for the work, Vendors should visit Roll Room of pouch Packing at Amulfed dairy, Bhat Village</u> for proper understanding of the Scope of Work and location of the proposed Mezzanine floor.</p> <p><b>Vendors who have quoted without Site visit to Amul fed Dairy, their quotes will not consider</b></p>	
<u>3</u>	<p><b>Total Mezzanine Floor Proposed Area : 45 Sq -Mts +/- 5 %</b></p> <p><b>Site Name -Roll Room at pouch packing of Amul fed Dairy</b></p> <p><b>Room Temperature - Ambient</b></p> <p><b>Room Width -4850 mm</b> <b>Room length - 9010 mm</b> Clear height of Mezzanine floor from the Ground Floor is 2290 mm plus or minus 5mm as per existing wall and floor slope (Top of Mezzanine Floor).</p> <p>Maximum Load carrying capacity: 1000 Kg UDL per Square meter + 10 % tolerance. Total Load bearing capacity of overall Mezzanine floor area: 30 to 35 Tons. Existing Tile flooring (20MM Tile) of the Roll Room (where Mezzanine floor is planned) is with average thickness of 5 to 6 inches RCC. There may be a slope of approximately 1 to 2 inches from one end to another end of the stores. While fabricating the vertical supports, these points should be taken care by the vendor. Vendor has to consider minimum vertical support for better and easy movement of Hand Pallet Trolley.</p>	
<u>4</u>	<p><b>Scope of Work:</b> Design, Fabrication, Supply, Installation &amp; Commissioning of Mezzanine flooring system along with Slotted sheets /Solid Sheet enable</p>	

Plot No. 35, Nr. Indira Bridge, Ahmedabad-Gandhinagar Highway, Village: Bhat, Dist.:Gandhinagar, PIN 382428

Tel. No. (+91-79) 23969055 – 58, Fax No. (+91-79) 23969059

Website: www.amul.com

# AmulFed Dairy

A UNIT OF GUJARAT CO-OPERATIVE MILK MARKETING FEDERATION LIMITED

(Previously Known as Mother Dairy, Gandhinagar)

	to movement of Hand Pallet trolley for movement of loaded Pallets without disturbing the ground floor on turnkey basis as per the technical details given below.	
<u>5</u>	The complete Mezzanine floor system shall be of Bolted design so that it can be dismantled in total whenever it is not required. All the fasteners required for establishing the Mezzanine floor shall be of suitable size and SS304 with NY lock nut and Check NUT to bear the load as per requirement. All the fasteners shall be tightened properly by using suitable capacity torque wrenches as per manufacturers design to ensure the stability of the entire structure.	
<u>6</u>	After placement of order, Vendor has to submit his final drawing for taking approval from the User Department before starting the fabrication work.	
<u>7</u>	Suppliers are requested to submit the detailed material specification and dimensions of material going to be used in erection of structure w.r.t Columns, Main Beams, Auxiliary, Beams, Staircase, Safety Rails . etc	
<u>8</u>	Finish: The entire Mezzanine floor structures to be neatly finished with Powder coating and Floor Shall be HDG (Hot Deep Galvanized)	
<u>9</u>	Railings: All four side of the Mezzanine floor shall be provided with Safety railings up to the height of 3 feet above the Mezzanine floor.	
<u>10</u>	<u>Stair case:</u> one locations of the Mezzanine floor, Stairs to be provided for going to the Mezzanine floor. The location for the stairs will be decide during Site Visit or at Final Approval The total width of the stairs shall not be less than 3 feet and height of each step shall not be more than 6 inches. Stairs steps to be provided with chequer plates of thickness not less than 5 mm with proper rigid support. Load carrying capacity of each step of the stairs shall not be less than 100 Kgs.	
<u>11</u>	Material test certificates w.r.t steel materials used for establishing the mezzanine floor has to be provided by the supplier. Before starting of the work	
<u>12</u>	After approval of the schematic layout, design	

(Previously Known as Mother Dairy, Gandhinagar)

	drawing of the Mezzanine floor has to be got it certified by the vendor from the chartered Civil Structural Engineer for the load mentioned above before starting of the fabrication work. After completion of the work also, vendor has to carry out the Structure Stability certificate of the Mezzanine floor for which it is designed and certification from the chartered civil engineer	
<b>13</b>	<b><u>Delivery:</u></b> Design, Approval, Fabrication, Supply, Installation, Commissioning & Testing of the entire Mezzanine floor to be completed <u>within two Months</u> from the date of release of PO / site clearance by Amul fed Dairy	
<b>14</b>	All the required tools, tackles, ladders, scaffolding, safety gadgets viz, helmet, gloves, mask, safety belts, trained manpower required to complete the work in total has to be arranged by the vendor.	
<b>15</b>	Welding work is allowed on sight if required in roll Room with proper advance planning and can be done with prior approval from - Safety Dept.	
<b>16</b>	If Any minor civil works to be carried out while installing the mezzanine floor has to be done by the vendor only.	
<b>17</b>	Required electrical power for carrying out the work shall be provided by AmulFed at a free cost.	
<b>18</b>	Vendor & his workers have to strictly adhere to the safety norms of AmulFed Dairy while working inside the factory. It is the responsibility of the Vendor to ensure the safety of their work and necessary appliances such as safety belts, shoes, helmets, goggles, gloves, belts etc. While carrying out the work at height, vendor should take necessary work permit and work at height, hot working permissions as per the applicable safety norms.	
<b>19</b>	Required relevant Hydraulic lifter for pallet Movement from Ground floor to Mezzanine floor. Maximum load of Pallet is @1Ton	
<b>20</b>	Required hydraulic cylinder Guarantee of five years with its maintenance	

Note :

- Rates must be inclusive of all.
- FOR Dairy.
- Floor leveling plates/shims in scope of vendor.



(Previously Known as Mother Dairy, Gandhinagar)

**On Letter Head of Vendor / Customer.**

To,  
General Manager  
AmulFed Dairy (A Unit of GCMMF Ltd.)  
Village:- Bhat,  
Near Indira Bridge,  
Gandhinagar-382 428

Dear Sir,

**Sub : Fund Transfer Payments.**

I/we request and authorise you to effect Fund Transfer Payment to my / our Bank account as per the details given below (Please map our account in your SAP):

Vendor Name:- : \_\_\_\_\_  
Vendor Code : \_\_\_\_\_  
Bank Account Name : \_\_\_\_\_  
Bank Account Number : \_\_\_\_\_  
Branch Name & Address of Bank: \_\_\_\_\_  
Email Id : \_\_\_\_\_  
Permanent A/c Number (PAN) : \_\_\_\_\_  
Name of the Auth signatory : \_\_\_\_\_  
Contact Person : \_\_\_\_\_  
Contact Number : \_\_\_\_\_  
IFSC code : \_\_\_\_\_  
MICR Code : \_\_\_\_\_  
Type of Account : Savings / Current / Cash Credit

I, hereby declare that the particulars given above are correct. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I hereby authorise Bank (as mentioned above) to credit my above-mentioned account with the amount of instalment and I agree to discharge the responsibility expected of me as a participant under the scheme.

Date: \_\_\_\_\_

Signature of Account Holder (s)

- Mandatory fields -cannot be left blank.
- Kindly attach a blank cancelled cheque with this mandate form.

---

**Bankers Attestation -**

**CERTIFIED THAT THE PARTICULARS FURNISHED ABOVE ARE CORRECT AS PER OUR RECORDS.**

BANK STAMP

DATE : \_\_\_\_\_

\_\_\_\_\_  
SIGNATURE OF BANK OFFICIAL